



**NOTES**

1. THE ENTIRE EXTENTS OF THE EXCAVATED TRENCH SHALL BE BACKFILLED WITH 1"-0 CRUSHED AGGREGATE TO FINISHED GRADE. SEE STANDARD DRAWING NO. 205.
2. BASE SHALL BE PRECAST CONCRETE CONFORMING TO THE REQUIREMENTS OF ASTM C478.

<b>CITY OF ALBANY, OREGON</b>		
<b>PUBLIC WORKS DEPARTMENT</b>		
<b>STANDARD SANITARY SEWER/ STORMDRAIN MAINLINE 24" MINI-MANHOLE CLEANOUT DETAIL</b>		
NO SCALE	FEBRUARY 2024	NO. 416